

1

Design Review Board Study Session

TO: DESIGN REVIEW BOARD

FROM: ROBERT (BOB) CARAVONA, AICP, SENIOR PLANNER

(480) 503-6812, BOB.CARAVONA@GILBERTAZ.GOV

THROUGH: CATHERINE LORBEER, AICP, PRINCIPAL PLANNER

(480) 503-6016, CATHERINE.LORBEER@GILBERTAZ.GOV

MEETING DATE: DECEMBER 11, 2014

SUBJECT: DR14-39 PET DEPOT

STRATEGIC INITIATIVE: Economic Development

To allow for the development of a commercial pad within an existing shopping center.

REQUEST

DR14-39, Pet Depot: site plan, landscape, grading and drainage, elevations, floor plans, lighting, colors and materials for a new 10,214 square foot building on approximately 1.1 acres located at the southeast corner of Market Street and Pecos Boulevard zoned Regional Commercial (RC) with a Planned Area Development (PAD) overlay (Crossroads Center).

RECOMMENDED MOTION

Request for input only. No motion required.

APPLICANT/OWNER

ID Studio 4 Company: Company: Pet Depot Name: Name: Cheryl Vernon Alex Ramon Address: 15650 N. Black Canyon Hwy. Address: 1134 S. Porter Court Suite B-235

Gilbert, AZ 85296

Phoenix, AZ 85053

602-938-1452 Phone: Phone: 480-612-2153

Email: ARamon@idstudio4.com Email: brucecherryl@hotmail.com

BACKGROUND/DISCUSSION

History:

Date	Action
1/25/99	Town Council approved Z98-27 by adopting Ordinance No. 1142, rezoning
	approximately 523 acres from R-43 (Maricopa County Rural Residential) to
	PAD (Planned Area Development) with the underlying zoning designation of C-
	2 (General Commercial).
11/16/99	Town Council approved Ordinance No. 1230 by adding and rezoning 63 acres
	from R-43 (Maricopa County Rural) to C-2 with underlying PAD; adding new
	conditions; amending the development plan of Crossroads Center Planned Area
	Development and repeal conflicting ordinances.
12/11/03	Design Review Board approved DR03-97, Phase II at Santan Village
	Marketplace.
03/09/06	Design Review Board approved a master sign program and entry features for
	Parcels G-1 and G-2 at Santan Village Marketplace (DR05-139).
12/14/06	Design Review Board approved DR06-102, the Final Design Review for the
	landscape palette and design, and the design and location of entry
	monumentation in a 20 foot wide multi-use easement adjacent to the rights-of-
	way associated with Parcel G-2 of Santan Village Marketplace. The rights-of-
	way include portions of Santan Village Parkway, Market Street, and Pecos Road.

Overview: Pet Depot is a comprehensive pet retail, veterinarian and kennel service to be located in a newly constructed 10,214 square foot retail building with a 1,353 square foot outdoor pet play area.

The site is a portion of a Replat of Lot 1B, 'Santan Village Marketplace Parcel G-2'. The applicant's intent is to subdivide the site from the parent parcel. The site is currently vacant as is much of the surrounding land with the exception of Costco to the south. The existing zoning for the site is Regional Commercial and the proposed use is consistent the Crossroads PAD, Santan Village Development Plan and the zoned land use for Regional Commercial.

Surrounding Land Use & Zoning Designations:

	Existing Land Use Category	Existing Zoning	Existing Use
North	Regional Commercial (RC)	Regional Commercial (RC)	Vacant

South	Regional Commercial (RC)	Regional Commercial (RC)	Access Drive/Parking/Costco
East	Regional Commercial (RC)	Regional Commercial (RC)	Vacant/Parking
West	Regional Commercial (RC)	Regional Commercial (RC)	Access Drive/Vacant (DR14-42, Costa Vida proposed)
Site	Regional Commercial (RC)	Regional Commercial (RC)	Vacant

Adopted Ordinance No. 1142 created the Crossroads Planned Area Development which expressively permitted certain uses, established design guidelines and adopted development standards that were unique to the development and, in certain instances, expressively deferred to the Town code at the time of adoption (ULDC for properties zoned C-2). Ordinance No. 1230 amended Ordinance No. 1142 by zoning additional lands and adding new conditions. Therefore, the project has been reviewed under The Crossroads PAD (Z98-27 and Ordinance Nos. 1142 and 1230), Table 1.65 Bulk, Building and Landscape Setback Requirements for Non-Residential Districts and when deferred to Town regulation, the ULDC (C-2) and commercial guidelines.

Project Data Table

Standards	Ordinance No. 1230	Proposed
Maximum Height (ft.) / (Stories)	40'	25'-2"
Building Setback		
Front	0'	70'-1"
Side	0'	28' / 70'-3"
Rear	0'	23'-6"
Floor Area Ratio Maximum	0.5	0.21

DISCUSSION

Elevation and Color

The exterior is stucco accented with ledgestone. The building's color is Bungalow Taupe accented with a slightly darker shade of Desert Gray in the sign area over the main entrance as well as upon appropriately placed architectural features on the rear elevation. A Coco Brown split face CMU capped with a Superlit Coco Brown Smooth Face veneer provides a substantial appearing foundation to the structure, which is accented with Cultured Stone Country Ledgestone Mojave Stone Accent.

The windows have precast window features and metal awning trellises as found in other recent nearby development. The trellises, in conjunction with the simple black lettering on the front elevation, contribute favorably to the overall design.

The floor plan shows an outdoor play area for animals. The play area is hidden from view and enclosed behind a twelve foot (12') wall, which is integrated into the building design along the southwest elevation.

Site Plan

The site plan complies with the Planned Area Development setback requirements and parking requirements of 41 spaces, 2 accessible spaces and 4 spaces for bikes. The applicant responded to staff's request by moving the trash enclosure from the northern drive to the northeast corner of the property. In addition, the applicant responded by shifting the building northward to accommodate the site distances, which will result in a four-way signed intersection.

Lighting

Three new parking light fixtures and fifteen attached lighting fixtures comply with the lighting standards.

Grading and Drainage

To be reviewed by Town Engineer.

Signs

Signs are not part of this request and shall be made under a separate application.

REQUESTED INPUT

Any input or comments regarding building elevations.

Robert M. Course

Respectfully submitted,


Robert M. Caravona, AICP

Senior Planner


Attachments and Enclosures:

- 1. Vicinity Map
- 2. Site Plan
- 3. Landscape Plan
- 4. Elevations
- 5. Floor Plans
- 6. Lighting
- 7. Colors and Materials

DR14-39 Attachment 1: Vicinity Map December 11, 2014



Vicinity Map



Site Data


Site Area: 356,938 S.F. (8.2 AC.)

Building Area: 39,088 S.F.

Coverage: 11.0%

Parking Provided: 333 Spaces

Overall Parking Ratio: 8.5 / 1,000







SOUTH MARKET STREET


SanTan **Development Group** EXISTING SIGN PECOS

S.W.C. Williams Field Road and San Tan Village Parkway Gilbert, Arizona



Butler Design Group, Inc architects & planners





SCALE: 1" = 20'-0"

PLANTING KEY NOTES

- PROPERTY LINE / RIGHT OF WAY LINE
- DECOMPOSED GRANITE IN ALL PLANTING AREAS
- (3) SIDEWALK
- (4) ACCESSIBLE RAMP. SEE CIVIL ENG. PLANS.
- (5) LIGHT POLE, SEE PHOTOMETRIC PLANS

- NOTES:

 1. CONTRACTOR TO VERIFY ALL QUANTITIES. CONTRACTOR TO PROVIDE DECOMPOSED GRANITE
- SAMPLES TO LANDSCAPE ARCHITECT FOR APPROVAL MAINTAIN 3' TO 5' TREE AND SHRUB CLEARANCE FROM WALLS. UNLESS OTHERWISE APPROVED BY THE
- GEOTECHNICAL ENGINEER. MAINTAIN 1' TO 2' TREE AND SHRUB CLEARANCE FROM SIDEWALKS. UNLESS OTHERWISE APPROVED BY THE GEOTECHNICAL ENGINEER.
- ALL TREES LOCATED IN TURF AREAS SHALL HAVE A TREE GUARD.
- TREES ADJACENT TO PEDESTRIAN WALKWAYS SHOULD
- HAVE A MINIMUM CANOPY CLEARANCE OF 6'-8".
 ALL MATURE TREES AND PALM CANOPIES MUST BE A MINIMUM OF 5' FROM ANY BUILDING WALLS OR

BUILDING WINDOWS.

SYMBOL	BOTANICAL NAME	COMMON NAME	SIZE	QTY	COMMENTS
$\overline{}$	TREES				
\triangleleft	CERCIDIUM 'HYBRID' 'DESERT MUSEUM'	DESERT MUSEUM	24" BOX 15" BOX	3 3	STAKE IN PLACE
+	CAESALPINIA CACALACO 'SMOOTHIE'	THORNLESS CASCALOTE	24" BOX 15" BOX	1	STAKE IN PLACE
\mathfrak{D}	ACACIA SMALLII	TEXAS MOUNTAIN LAUREL	24" BOX 15" BOX	4 3	STAKE IN PLACE
U	SHRUBS	_	10 50%	Ü	
	LEUCOPHYLLUM LANGMANIAE	'RIO BRAVO' TEXAS SAGE	5 GAL.	2	PLANT AT 7' O.C.
	ACCENTS	_			
₩	DASYLIRION WHEELERI	DESERT SPOON	5 GAL.	35	PLANT AT 5' O.C.
⊕	MUHLENBERGIA CAPILLARIS	REGAL MIST	5 GAL.	13	PLANT AT 3' O.C.
	GROUNDCOVER	_			
	LANTANA MONTEVIDENSIS	GOLD LANTANA	1 GAL.	58	PLANT AT 4' O.C.
	LANTANA MONTEVIDENSIS	PURPLE LANTANA	1 GAL.	92	PLANT AT 2' O.C.
	INERT GROUNDCOVER				
2	DECOMPOSED GRANITE	"EXPRESS ROSE"	1/2" SCREENED	7,315 SQ. FT.	2" MIN. DEPTH IN ALL PLANTERS

DR14-39 **Attachment 3: Landscape Plan December 11, 2014**

GENERAL PLANTING NOTES

- THE SUB-CONTRACTOR SHALL MARK AND CONFIRM LOCATIONS OF UNDERGROUND UTILITIES PRIOR TO EXCAVATION. CONFLICTS SHALL BE REPORTED TO THE LANDSCAPE
- 2. PLANT MATERIALS SPECIFIED SHALL BE SUBJECT TO HAND SELECTION BY THE LANDSCAPE ARCHITECT AT THE NURSERY
- FINISH GRADE OR TOP OF D.G. (WHICHEVER IS HIGHER) SHALL BE 1-1/2" BELOW ADJACENT CONCRETE OR OTHER PAVED SURFACES.
- LANDSCAPE CONTRACTOR IS RESPONSIBLE FOR ALL PLANTS SHOWN ON PLANTING PLAN.
 LANDSCAPE CONTRACTOR SHALL BE RESPONSIBLE FOR ACCURATE PLANT COUNTS.
- CONTRACTOR TO STAKE ALL TREE, PALM, AND SHRUB LOCATIONS FOR LANDSCAPE ARCHITECT'S APPROVAL PRIOR TO PLANTING.
- 6. LANDSCAPE ARCHITECT WILL NOT BE RESPONSIBLE FOR LOCATION AND PLACEMENT OF TREES AND PALMS UNLESS THE LOCATION WAS APPROVED BY LANDSCAPE ARCHITECT.
- ALL MATURE TREE AND PALM CANOPIES MUST BE A MINIMUM OF 5' FROM ANY BUILDING
- 8. ALL PLANT MATERIALS SHALL BE SIZED ACCORDING TO THE ARIZONA NURSERY ASSOCIATION STANDARDS. PLANT MATERIAL SIZES NOT ESTABLISHED PER A.N.A. STANDARDS SHALL BE SIZED ACCORDING TO THE AMERICAN ASSOCIATION OF
- 9. ACID ETCH AS REQUIRED IMPERVIOUS SOILS AT TREE LOCATIONS TO ENSURE PLANT HEALTH.
- 10. SUB-CONTRACTOR TO TREAT ALL D.G. AREAS WITHIN LINE OF CONTRACT WITH ONE FINAL APPLICATION OF APPROVED PRE-EMERGENT HERBICIDE AT THE TIME OF ACCEPTANCE BY THE OWNER.
- 11. CACTI SHALL RECEIVE NO SUPPLEMENTAL IRRIGATION.
- 12. NO PLANT SUBSTITUTIONS, TYPE, OR QUANTITY DEVIATIONS FROM THE APPROVED LANDSCAPE OR IRRIGATION PLANS WITHOUT PERMISSION FROM THE LANDSCAPE
- 13. ALL R.O.W. PLANT MATERIAL TO BE IN COMPLIANCE WITH THE ARIZONA DEPARTMENT OF WATER RESOURCES LOW WATER USE PLANT LIST.
- 14. EXISTING TREES AND SHRUBS IN R.O.W. TO REMAIN OR BE RELOCATED BY CONTRACTOR. ANY PLANT MATERIAL DAMAGED OR DESTROYED WILL BE REPLACED IN KIND BY THE CONTRACTOR.
- 15. ALL LANDSCAPE AREAS SHALL RECEIVE 2" D.G. UNLESS NOTED. COLOR TO BE SELECTED
- 16. ROUGH GRADING TO WITHIN +0.10 FOOT, INCLUDING ALL BERMS AND/OR SWALES AND RETENTION AREAS WILL BE PROVIDED BY BUILDER BEFORE PLANTING BEGINS.
- ANY DISCREPANCIES FOUND BETWEEN PLANS, SPECIFICATIONS, AND SITE SHALL BE BROUGHT TO THE ATTENTION OF THE LANDSCAPE ARCHITECT FOR RESOLUTION.
- 18. LANDSCAPE ARCHITECT HAS THE OPTION OF ACCEPTANCE OR REJECTION OF ANY PLANT MATERIALS DEEMED UNACCEPTABLE UPON DELIVERY TO SITE.
- 19. ACKNOWLEDGE REQUIREMENT OF COUNTY DUST CONTROL PERMIT AND LANDSCAPE PERMIT FOR ALL LANDSCAPE WORK WITHIN THE PROJECT ON RESIDENTIAL, COMMERCIAL, AND INDUSTRIAL SUBDIVISIONS.
- 20. TREES, SHRUBS, VINES, GROUNDCOVER, AND TURF WHICH HAVE TO BE REPLACED UNDER TERMS OF THE GUARANTEE, SHALL BE GUARANTEED FOR AN ADDITIONAL SIXTY (60) DAYS FROM THE DATE OF REPLACEMENT.
- 21. ALL SIGNS AND MONUMENT WALLS REQUIRE A SEPARATE BUILDING APPROVAL AND
- 22. THE CONTRACTOR SHALL PROVIDE ALL REQUIRED SHOP DRAWINGS TO THE LANDSCAPE ARCHITECT FOR REVIEW AND APPROVAL PRIOR TO THE BEGINNING OF CONSTRUCTION. REQUIRED SHOP DRAWING MAY INCLUDE BUT NOT LIMITED TO WALLS, COLUMNS, ENTRY GATES, POOL FENCE ANDIOR WATER FEATURES. SHOULD A DISPUTE ARISE WITH ANY DESIGN ELEMENT REQUIRING SHOP DRAWINGS, THE LANDSCAPE ARCHITECT SHALL ONLY ASSUME RESPONSIBILITY IF THE SHOP DRAWINGS IN QUESTION HAVE BEEN REVIEWED AND APPROVED BY THE LANDSCAPE ARCHITECT.
- 23. ALL TREES WITHIN THE SIGHT TRIANGLE AND DISTANCE AREAS SHALL BE MAINTAINED TO A MINIMUM CANOPY CLEARANCE OF 7'-0".



15650 N. BLACK CANYON HWY. SUITE B-235 PHOENIX, AZ 85053 TEL: 602.938.1452 WWW.IDSTUDIO4.COM

ISSUE FOR CONSTRUCTION

DEPOT




_	MIC	DESCRIPTION		
10	H07-14	TOW	N OF GILBERT PRELIMINARY PLAT	
7	DAT	Е	DESCRIPTION	


WCC14003

PLAN **PLANTING**






Attachment 5: Floor Plans December 11, 2014





SHEET TITLE:


A1.1

PET DEPOT
SAN TAN VILLAGE MARKETPLACE
GILBERT, ARIZONA 85206









DR14-39 Attachment 6: Lighting December 11, 2014



ID STUDIO 4, LLC
15650 N. BLACK CANYON HWY.
SUITE 8-25
PHOENIX, AZ 85053
TE: 602,938,1452
WWW.IDSTUDIO4.COM

	DATE	DESC	CRIPTION
_		_	
-			
Δ	DAT	E	DESCRIPTION
-			
-			
-			
_			
_			
SH	EET T	TLE	
SITE LIGHTING CUT SHEETS			

0

DEP(

PET

E0.0

PROJECT NUMBER:

SHEET NUMBER:

WCC14003



ID STUDIO 4, LLC 15650 N. BLACK CANYON H' SUITE B-235 PHOENIX, AZ 85053 TEL: 602.938.1452 WWW.IDSTUDIO4.COM

PET DEPOT GILBERT,

PHOTOMETRIC SITE PLAN

SHEET NUMBER:

E1.1

WCC14003



Integrated Design Engineering Architecture

Paint:	Paint:
Dunn Edwards DE6172 Bungalow Taupe	Dunn Edwards DEC760 Desert Gray
Field Color	Accent Color
Paint:	Paint:
Dunn Edwards DE6171 Sand Dollar	Dunn Edwards DEA187 Black
Trim Color	Trellis & Exterior Lights
C.M.U. Veneer:	C.M.U. Veneer:
Superlite Coco Brown	Superlite Coco Brown
Split Face	Smooth Face
THE PERSON NAMED IN COLUMN TWO IS NOT THE PERSON NAMED IN COLUMN TWO IS NAMED IN COLUMN TW	
Stone Veneer:	Storefront Glass:
Cultured Stone Country Ledgestone Mojave	Solarban 60 Insulated Clear
Cultured Stone Country Ledgestone Mojave	Solarban 60 Insulated Clear
Cultured Stone Country Ledgestone Mojave	Solarban 60 Insulated Clear
Cultured Stone Country Ledgestone Mojave	Solarban 60 Insulated Clear
Cultured Stone Country Ledgestone Mojave	Solarban 60 Insulated Clear

Material Board - Pet Depot Santan Village Gilbert, Arizona